



ADUDIO Collection Specifications

APPLICABLE CURRENT BUILDING CODES

2019

California Residential Code
California Mechanical Code
CalGreen

California Plumbing Code
California Energy Code – Title-24

Item	Description
Exterior:	
Siding	Fiber Cement, Horizontal Lap, Cedar-grain w/ 8" reveal
Siding Underlayment	Tyvek Residential HomeWrap
Paint	PPG® Exterior Paint CalGreen compliant Low or No VOCs
Paint Color	Two Colors, Body & Trim; Add an Accent Color (Upgrade)
Trim	Fiber Cement 3.5" with 5.5" header on top
Fascia	Fiber Cement 7.25" Trim
Soffit	Fiber Cement Vented Smooth
Windows	Single-Hung Vinyl, Low-E, Dual-Glazed, w/ Argon gas
Window Options	Transom or Clerestory windows (Upgrade)
Window Grid	No grids (standard); grids available (Upgrade)
Roofing	Owens-Corning - Oakridge Composition Shingles (Limited Lifetime Warranty, standard) Cool Roof Shingles (Upgrade); Metal Roofing (Upgrade)
Roofing Underlayment	30-LB Felt
WUI High Fire Specs	Wildland Urban Interface High-Fire Hazard Zone specifications, as required by CalFire or if requested by any Client. (Upgrade)
Front Door	36" x 80" 3-Panel Flat Craftsman Fiberglass painted entry door
Front Door Option	Wood-style Grain Fiberglass entry door or Half / Full Lite (Upgrades)
Front Door Hardware	Satin nickel exterior hardware with Thumb-open and Deadbolt

Crawl Space Access	By Site Contractor, in Exterior of Foundation Wall Interior Access in floor of home, if specified in PLANS (Upgrade)
Interior:	
Drywall Finish	Drywall hung, seams fire-taped behind cabinets and any covered areas. Textured Finish and all Interior Paint by Site Contractor (including taping seams)
Drywall Corners	Rounded Throughout
Paint	Interior Paint Shipped Loose for On-Site Application by Site Contractor. PPG® Paint Provided, CalGreen No VOC paints Color - Shasta White PPG® Pick color for the Paint Body Color, One max (Upgrade)
Paint Sheen	Walls and Ceiling in Bed/Living/Hallways - Eggshell Walls and Ceiling in Kitchen/Baths/Utility - Semi-Gloss Doors and Trim - Pure White Semi-Gloss Mudding, Texture & Painting to be done by Site Contractor
Interior Doors	White Raised 3-Panel, Hollow-Core (standard); Solid-Core (Upgrade)
Interior Door Hardware	Lever Knobs - Brushed Nickel
Door / Window Trim	Craftsman Package - 2.75" sides with 3.5" header piece
Baseboards	5.5" square
Closet Shelving	11.25" with Hanger Rod below
Window Sills	Craftsman Sill with trim and apron
Cabinets	European-style raised-panel or recessed-panel cabinetry with concealed hinges and hardware, 2" Crown Moulding on top 9 Styles and Colors to Choose from All Hardwood Face Frames and Doors with Solid Plywood Boxes
Cabinet Height	42" hanging wall cabinets; Add Soffit (Upgrade)
Doors & Drawers	Hardwood with Soft Close
Drawer Guides	Full Extension with Soft Close
Hardware	Knobs and Handles - Brushed Nickel

DEFINITIONS

Factory =	Your home is precision-built, indoors in a dry, controlled-environment.
Site Contractor =	A Licensed California Contractor who will provide labor and some materials to complete the required work at the construction site (in direct contract with you).
PLAN (OR) PLANS =	The complete set of Factory Built Housing (commonly called "Modular") plans approved by a State of California 3rd Party Design Approval Agency as complete and ready to construct in the Factory.
Standard =	Included in the base price for the Modular home
Upgrade =	Available for an Additional expense

Additional Options	Wine Storage, Wall China, Base Bookshelf, Pots/Pans Drawer, Built-in Trash Can, etc. (Upgrades)
Laundry Area	Plumbed and Wired for stacked washer-dryer by Site Contractor
Countertops	Granite in kitchen and all bathrooms Oversized islands, bars, or special areas (Upgrades)
Countertop Options	Custom Quartz, specialty granite, wood or others (Upgrades)
Backsplashes	4" Granite
Backsplash Options	7" Granite or full backsplash (Upgrades)
Attic Access	Per PLAN

Kitchen/Laundry:

Cabinets	European-style raised-panel or recessed-panel cabinetry with concealed hinges and hardware, 2" Crown Moulding on top All Hardwood Face Frames and Doors with Solid Plywood Boxes
Cabinet Height	42" hanging wall cabinets
Doors & Drawers	Hardwood with Soft Close
Drawer Guides	Full Extension with Soft Close
Hardware	Knobs and Handles - Brushed Nickel
Additional Options	Wine Storage, Wall China, Base Bookshelf, Pots/Pans Drawer, Built-in Trash Can, etc. (Upgrades)
Laundry Area	Plumbed and Wired for stacked washer-dryer by Site Contractor
Countertops	Granite in kitchen and all bathrooms Oversized islands, bars, or special areas (Upgrades) Custom Quartz, specialty granite, wood or others (Upgrades)
Backsplashes	4" Granite
Kitchen Sink	9" deep Stainless Steel Double Bowl
Kitchen Faucet	Single Lever Gooseneck with Sprayer in Brushed Nickel
Garbage Disposal	½ HP with continuous feed; InSinkErator (Upgrade)
Pantry Shelving	11.25" - Minimum 3 shelves with 1'-6" vertical spacing

Appliances

Range	Stainless Steel; Electric or Gas
--------------	----------------------------------

DEFINITIONS

Factory =	Your home is precision-built, indoors in a dry, controlled-environment.
Site Contractor =	A Licensed California Contractor who will provide labor and some materials to complete the required work at the construction site (in direct contract with you).
PLAN (OR) PLANS =	The complete set of Factory Built Housing (commonly called "Modular") plans approved by a State of California 3rd Party Design Approval Agency as complete and ready to construct in the Factory.
Standard =	Included in the base price for the Modular home
Upgrade =	Available for an Additional expense

Range Ventilation	Stainless Steel Electric Hood
Dishwasher	Stainless Steel
Refrigerator	Plumbed for ice-maker; Refrigerator By Client or Site Contractor
Microwave	Over Range Microwave substituted for Hood (Upgrade)
Washer and Dryer	None (standard); Washer / Dryer included (Upgrade)
Or, Omit All	Option to Omit Range, Hood, and Dishwasher for Credit

Bathroom:

Shower	Composite Shower Pan with Composite Wall Panels
Tub	Alcove Tub with Composite Panel Walls Substitute - Concrete Backer Board Prep for Tile instead of composite wall panels (NO COST)
Water Saving Fixtures	All Fixtures are EPA "WaterSense" and CalGreen Certified
Tub/Shower Faucets	Single Lever Diverter - Brushed Nickel
Shower Head Height	7', or height as requested; Rain Shower (Upgrade)
Lavy	Single China Sink with Overflow
Lavy Faucet	Single Handle Lavy Faucet, Brushed Nickel
Water Closet	Elongated, Dual-flush
Mirror	Beveled Edge, Above Sink
Medicine Cabinet	Recessed
Hardware	24" Towel Bar, Tissue Holder & Towel Ring in Brushed Nickel
Cabinets	European-style raised-panel or recessed-panel cabinetry with concealed hinges and hardware
Ventilation	Panasonic® Whisper Green Auto-on Humidistat Ventilation Fans

Electrical:

Main Panel	100 AMP Electrical Service.
Meter Panel option	Meter Base Panel on exterior wall (Upgrade)
Switches	Leviton Decora switches and outlets
Light Bulbs	LED integrated bulbs in all lighting fixtures
Exterior Entry Lights	(1) LED Wall Light per exterior door

DEFINITIONS

Factory =	Your home is precision-built, indoors in a dry, controlled-environment.
Site Contractor =	A Licensed California Contractor who will provide labor and some materials to complete the required work at the construction site (in direct contract with you).
PLAN (OR) PLANS =	The complete set of Factory Built Housing (commonly called "Modular") plans approved by a State of California 3rd Party Design Approval Agency as complete and ready to construct in the Factory.
Standard =	Included in the base price for the Modular home
Upgrade =	Available for an Additional expense

Kitchen Area Lights	LED Recessed Lights (2-3)
USB Receptacle	(1) in Kitchen Area to charge electronic devices
Hall Lighting	LED Recessed Light(s) (1-2)
Bathroom Vanity Light	2 or 3-Light, Brushed Nickel based on Vanity size, on Occupancy Sensor
Bedrooms Light	Ceiling Mounted Flush Light with Brushed Nickel Trim
Add Lighting option	Additional Recessed lights, Under/Over Cabinet Lighting (Upgrade)
Fans	Prep for fan (Upgrade), Fans by Site Contractor
Data Closet Prep	(1) Faceplate with Conduit Stubbed to the bottom of floor joists, no wire
Dryer Hookup	Recessed Box with dedicated vent to outside in floor system rim
Exterior Outlets	(1) GFCI with All-weather Covers; Additional GFIs (Upgrade)
Safety	ARC Fault Breakers throughout home
Detectors	Hard-wired Smoke & Carbon Monoxide Detectors per CODE

Plumbing:

Shut Off Valves	Angle-stops at all vanities and toilets; Whole-house shutoff at main inlet
Water Heater	40 Gallon Gas with Earthquake Bracing
-Tankless Gas option	Rinnai® (Upgrade)
-Tank Electric option	Rheem® Prestige 50 Gallon Electric EcoNet Enabled Hybrid (Upgrade)
-Exterior Access	Exterior door painted same color as siding (Upgrade)
Water Supply Plumbing	PEX piping - Strong, flexible, quiet, and corrosion-resistant
Waste Plumbing	ABS piping
Gas Lines	Gas Piping from fixture stubbed to bottom edge of floor structure
Utility Plumbing	Plumbing for Washer with shut-off valves and plumbing Gas Dryer
Gas Dryer Plumbing	If requested by Client in order, stubbed to bottom edge of floor structure
Hose Bibs	(1) included on exterior

Mechanical:

Air Handler	Mitsubishi Mini-Split Ducted Fan Coil Unit for Heat Pump (Electric)
Duct System	Insulated per Title 24 and Mechanical plans
Ventilation Whole House	Energy Recovery Ventilator (ERV) Fresh-air System
Ventilation Baths/Utility	Panasonic® Whisper Green Auto-on Humidistat Ventilation Fans

DEFINITIONS

Factory =	Your home is precision-built, indoors in a dry, controlled-environment.
Site Contractor =	A Licensed California Contractor who will provide labor and some materials to complete the required work at the construction site (in direct contract with you).
PLAN (OR) PLANS =	The complete set of Factory Built Housing (commonly called "Modular") plans approved by a State of California 3rd Party Design Approval Agency as complete and ready to construct in the Factory.
Standard =	Included in the base price for the Modular home
Upgrade =	Available for an Additional expense

Air Return	Ducted Air Return
Exterior Unit	Mitsubishi Condensing Unit for Heat Pump on pad outside of home by Site Contractor; Provided and installed on exterior wall mount (Upgrade)

Flooring:

Flooring Wet Areas	None (standard)
Flooring Dry Areas	None (standard)
All Flooring	Supplied and Installed by Site Contractor
Tile Prep	Backer-board Prep for Tile Floors (Upgrade)
Flooring Option	Waterproof Luxury Vinyl Plank with underlayment (Upgrade)

Décor:

Window Coverings	None
Blinds	None

Structural:

Floor Joist	2X10 or 2X12 Double Rims with Floor Joists; Floor Trusses (Upgrade)
Floor Decking	23/32 Tongue & Groove OSB
Exterior Walls	2X6 - 16" On Center
Wall Height	8' standard; 9' (Upgrade)
Interior Walls	2X4 (minimum)
Roof Pitch & Load	3/12 Roof Pitch with 30 lb roof load, or per PLANS Steeper Roof Pitch, Vaulted Ceilings, or High Snow Load roofs (Upgrades)
Roof Trusses	24" On Center with 7/16" OSB roof sheathing
Eaves & Overhangs	12" Per Plan Longer eaves or ship loose kit per PLANS (Upgrade)
Ceiling	Flat throughout Cove/Trey or Vaulted per PLANS (Upgrade)

Fire Sprinklers:

Project & PLAN Specific Engineered Design (Upgrade)

DEFINITIONS

Factory =	Your home is precision-built, indoors in a dry, controlled-environment.
Site Contractor =	A Licensed California Contractor who will provide labor and some materials to complete the required work at the construction site (in direct contract with you).
PLAN (OR) PLANS =	The complete set of Factory Built Housing (commonly called "Modular") plans approved by a State of California 3rd Party Design Approval Agency as complete and ready to construct in the Factory.
Standard =	Included in the base price for the Modular home
Upgrade =	Available for an Additional expense

Energy Efficiency:

Insulation	EcoBatt® formaldehyde-free insulation from Knauf
- Floor	R-30
- Walls	R-19
- Ceiling/Roof	R-38
Air & Vapor Barrier	Sill Seal with Vapor Barrier

Covered Porch

Per PLAN if built in Factory (**Upgrade**)
Deck Framing - Pressure Treated 2x
Decking - Composite
Square Baluster - Composite
Porch Columns - Craftsman style
Fiber Cement ceiling with 2 recessed LED Lights

Other Options:

From Your Imagination

Please Just Ask! The core mission of Cutting Edge Homes is to build a home that you will simply love. We want to provide options so that you are happy with your home after you move in, turning your imagination into a beautiful home for your family. If there is something that you absolutely must have in your home please ask and we will do everything that we can to accommodate you. There are limitations to what we can provide in the Factory, but we can modify the specifications so that anything we cannot install in the Factory can be done by the Site Contractor.

DEFINITIONS

Factory =	Your home is precision-built, indoors in a dry, controlled-environment.
Site Contractor =	A Licensed California Contractor who will provide labor and some materials to complete the required work at the construction site (in direct contract with you).
PLAN (OR) PLANS =	The complete set of Factory Built Housing (commonly called "Modular") plans approved by a State of California 3rd Party Design Approval Agency as complete and ready to construct in the Factory.
Standard =	Included in the base price for the Modular home
Upgrade =	Available for an Additional expense