



Cape Cod Series Specifications

APPLICABLE CURRENT BUILDING CODES

2019

California Residential Code
 California Mechanical Code
 CalGreen
 California Plumbing Code
 California Energy Code – Title-24

Item	Description
Exterior:	
Siding	<p>Option 1: LP Smartside Vertical 8" Groove Panel Siding Installed in Factory (as much as possible and practical)</p> <p>Option 2: Fiber Cement, Horizontal Lap, Cedar-grain with 7-8" Reveal Shipped Loose for Install On-Site by Others</p>
Siding Underlayment	Tyvek Residential HomeWrap
Paint	Exterior Paint to be Provided and Applied On-Site by Others
Trim	3.5"
Fascia	5.5"
Soffit	LP Smartside 8" Groove Panel
Windows	Horizontal Sliding Vinyl, Low-E, Dual-Glazed, w/ Argon gas
Window Grid	No grids (standard); grids available (Upgrade)
Roof	Shipped Loose are the Roof Rafters and Sheathing. All other roofing materials are to be provided by and installed by on-site contractor.
Dormers	Not Included (by Others)
WUI High Fire Specs	Wildland Urban Interface High-Fire Hazard Zone specifications, as required by CalFire or if requested by any Client. (Upgrade)
Front Door	36" x 80" Fiberglass entry door
Front Door Option	Wood-style Grain Fiberglass entry door or Half / Full Lite (Upgrades)

Front Door Hardware	Satin nickel exterior hardware with Thumb-open and Deadbolt
Rear Door	32" x 80" 3-Panel Flat Craftsman Fiberglass painted exterior door
Rear Door Hardware	Satin nickel, lever handle with Deadbolt
Crawl Space Access	By Site Contractor, in Exterior of Foundation Wall Interior Access in floor of home, if specified in PLANS (Upgrade)

Interior:

Drywall Finish	Drywall hung, seams fire-taped behind cabinets and any covered areas. Texture, Finish and all Interior Paint by Site Contractor (including taping seams & mudding)
Drywall Corners	Rounded Throughout
Paint	Interior Paint to be Provided and Applied On-Site by Others
Interior Doors	White Raised 6-Panel, Hollow-Core (standard); Solid-Core (Upgrade)
Interior Door Hardware	Lever Knobs - Brushed Nickel
Door / Window Trim	Craftsman Package - 2.75" sides with 3.5" header piece
Baseboards	5.5" square
Closet Shelving	11.25" with Hanger Rod below
Cabinets	European-style raised-panel or recessed-panel cabinetry with concealed hinges and hardware, 2" Crown Moulding on top 5 Styles and Colors to Choose from All Hardwood Face Frames and Doors with Solid Plywood Boxes
Cabinet Height	42" hanging wall cabinets; Add Soffit (Upgrade)
Doors & Drawers	Hardwood with Soft Close
Drawer Guides	Full Extension with Soft Close
Hardware	Knobs and Handles - Brushed Nickel
Additional Options	Built-in Oven, Wine Storage, Wall China, Base Bookshelf, Lazy Susan, Pots/Pans Drawer, Built-in Trash Can, etc. (Upgrades) Custom Cabinet Design with 3D renderings (Upgrade)
Attic Access	Per PLAN

DEFINITIONS	
Factory =	Your home is precision-built, indoors in a dry, controlled-environment.
Site Contractor =	A Licensed California Contractor who will provide labor and some materials to complete the required work at the construction site (in direct contract with you).
PLAN (OR) PLANS =	The complete set of Factory Built Housing (commonly called "Modular") plans approved by a State of California 3rd Party Design Approval Agency as complete and ready to construct in the Factory.
Standard =	Included in the base price for the Modular home
Upgrade =	Available for an Additional expense

Kitchen/Laundry:

Laundry Room	Recessed Washer Box with electric or gas dryer hook-up
Laundry Room Options	Cabinet over washer/dryer, Linen cabinet, Laundry sink with Base-cabinet and granite countertops (Upgrades)
Countertops	Granite in kitchen and all bathrooms Custom Quartz, specialty granite, wood or others (Upgrades) Islands, bars, or special areas (Upgrades)
Backsplashes	4" Granite, 7" Granite or full backsplash (Upgrades)
Kitchen Sink	9" deep Stainless Steel Double Bowl
Kitchen Faucet	Single Lever Gooseneck with Sprayer in Brushed Nickel
Garbage Disposal	½ HP with continuous feed; InSinkErator (Upgrade)
Pantry Shelving	11.25" - Minimum 3 shelves with 1'-6" vertical spacing

Appliances

Range	Prepped for Electric Range (Range Not Included) (Upgrade)
Range Ventilation	Electric Hood
Dishwasher	Cut-out for dishwasher provided, if Requested (D/W Not Included) (Upgrade)
Refrigerator Prep	Plumbed for ice-maker; Refrigerator By Client or Site Contractor
Microwave	Over Range Microwave substituted for Hood (Upgrade)
Washer and Dryer	None (standard)
Or, Omit All	Option to Omit Hood and Dishwasher

Master Bath:

Shower	Composite Shower Pan with Concrete Backer Board Prep for Tile (Tile by others)
Shower Upgrade	Substitute Composite Wall Panels for Concrete Backer board (Upgrade)
Tub	Alcove Tub with Composite Panel Walls Substitute - Concrete Backer Board Prep for Tile instead of composite wall panels (Upgrade)

DEFINITIONS

Factory =	Your home is precision-built, indoors in a dry, controlled-environment.
Site Contractor =	A Licensed California Contractor who will provide labor and some materials to complete the required work at the construction site (in direct contract with you).
PLAN (OR) PLANS =	The complete set of Factory Built Housing (commonly called "Modular") plans approved by a State of California 3rd Party Design Approval Agency as complete and ready to construct in the Factory.
Standard =	Included in the base price for the Modular home
Upgrade =	Available for an Additional expense

Drop-in Tub (per PLAN)	Oval Leisure Tub with granite tub deck/front, deck mounted faucet and 4" Granite backsplash (Upgrade)
Drop-in Tub options	Add electrical for Tub-jets or heater (Upgrade)
Water Saving Fixtures	All Fixtures are EPA "WaterSense" and CalGreen Certified
Tub/Shower Faucets	Single Lever Diverter - Brushed Nickel
Tub Faucets	Dual-Handle - Brushed Nickel
Shower Head Height	7', or height as requested
Lavy	Dual China Sink with Overflow
Lavy Faucet	Single Handle Lavy Faucet, Brushed Nickel
Water Closet	Elongated, Dual-flush
Mirror	Beveled Edge, Above Sink
Medicine Cabinet	Recessed
Hardware	24" Towel Bar, Tissue Holder & Towel Ring in Brushed Nickel
Cabinets	European-style raised-panel or recessed-panel cabinetry with concealed hinges and hardware
Ventilation	Panasonic® Whisper Green Auto-on Humidistat Ventilation Fans

Other Full Bathroom(s):

Tub/Shower	Alcove Tub with Composite Panel Walls Substitute - Concrete Backer Board Prep for Tile instead of composite wall panels (NO COST)
Water Saving Fixtures	All Fixtures are EPA "WaterSense" and CalGreen Certified
Tub/Shower Faucets	Single Lever Diverter - Brushed Nickel
Shower Head Height	7', or height as requested
Lavy	Single China Sink with Overflow
Lavy Faucet	Single Handle Lavy Faucet, Brushed Nickel
Water Closet	Elongated, Dual-flush
Mirror	Beveled Edge, Above Sink
Medicine Cabinet	Recessed
Hardware	24" Towel Bar, Tissue Holder & Towel Ring in Brushed Nickel

DEFINITIONS

Factory =	Your home is precision-built, indoors in a dry, controlled-environment.
Site Contractor =	A Licensed California Contractor who will provide labor and some materials to complete the required work at the construction site (in direct contract with you).
PLAN (OR) PLANS =	The complete set of Factory Built Housing (commonly called "Modular") plans approved by a State of California 3rd Party Design Approval Agency as complete and ready to construct in the Factory.
Standard =	Included in the base price for the Modular home
Upgrade =	Available for an Additional expense

Cabinets	European-style raised-panel or recessed-panel cabinetry with concealed hinges and hardware
Ventilation	Panasonic® Whisper Green Auto-on Humidistat Ventilation Fans
Electrical:	
Main Panel	200 AMP Electrical Service with Solar Prep and Electric Car Charging Circuit (if required).
Meter Panel option	Meter Base Panel on exterior wall (Upgrade)
Switches	Leviton Decora switches and outlets
Light Bulbs	LED integrated bulbs in all lighting fixtures
Exterior Entry Lights	(1) LED Wall Light per exterior door
Walk-in Closet Lights	LED Recessed Light(s) (1-2)
Kitchen Area Lights	LED Recessed Lights (5)
Dining Room	Junction box for a Chandelier with blocking; Chandelier by Site Contractor
USB Receptacle	(1) in Kitchen Area to charge electronic devices
Island or Bar Lighting	Canned LED Lights/Pendants (Upgrade)
Hall Lighting	LED Recessed Light(s) (1-2)
Laundry Lighting	LED Recessed Light(s) (1-2)
Bathroom Vanity Light	2 or 3-Light, Brushed Nickel based on Vanity size, on Occupancy Sensor
Bedrooms Light	Ceiling Mounted Flush Light with Brushed Nickel Trim
Stairwell Lighting	(1) Recessed Light at Bottom and Top, plus at landings per CODE
Add Lighting option	Additional Recessed lights, Under/Over Cabinet Lighting (Upgrade)
Fans	Prep for fan (Upgrade), Fans by Site Contractor
Data Closet Prep	(1) Faceplate with Conduit Stubbed to the bottom of floor joists, no wire
Dryer Hookup	Recessed Box with dedicated vent to outside in floor system rim
Exterior Outlets	(2) GFCI with All-weather Covers
Safety	ARC Fault Breakers throughout home
Detectors	Hard-wired Smoke & Carbon Monoxide Detectors per CODE

DEFINITIONS

Factory =	Your home is precision-built, indoors in a dry, controlled-environment.
Site Contractor =	A Licensed California Contractor who will provide labor and some materials to complete the required work at the construction site (in direct contract with you).
PLAN (OR) PLANS =	The complete set of Factory Built Housing (commonly called "Modular") plans approved by a State of California 3rd Party Design Approval Agency as complete and ready to construct in the Factory.
Standard =	Included in the base price for the Modular home
Upgrade =	Available for an Additional expense

Plumbing:

Shut Off Valves	Angle-stops at all vanities and toilets; Whole-house shutoff at main inlet
Water Heater	40 Gallon Gas with Earthquake Bracing
-Tankless Gas option	Rinnai® (Upgrade)
-Tank Electric option	Rheem® Prestige 50 Gallon Electric EcoNet Enabled Hybrid (Upgrade)
-Exterior Access	Exterior door painted same color as siding (Upgrade)
Water Supply Plumbing	PEX piping - Strong, flexible, quiet, and corrosion-resistant
Waste Plumbing	ABS piping
Gas Lines	Gas Piping from fixture stubbed to bottom edge of floor structure
Utility Plumbing	Plumbing for Washer with shut-off valves and plumbing Gas Dryer
Gas Dryer Plumbing	If requested by Client in order, stubbed to bottom edge of floor structure
Hose Bibs	(2) included on exterior

Mechanical:

Air Handler	Fan Coil Unit for Heat Pump (Electric)
Duct System	Insulated per Title 24 and Mechanical plans
Ventilation Whole House	Energy Recovery Ventilator (ERV) Fresh-air System
Ventilation Baths/Utility	Panasonic® Whisper Green Auto-on Humidistat Ventilation Fans
Air Return	Ducted Air Returns
Exterior Unit	Condensing Unit for Heat Pump on pad outside of home by Site Contractor / <u>Not</u> provided with Cutting Edge package
Mini-Split Heat Pump	Engineered item per PLANS, ducted or ductless (Upgrade)

Flooring:

Flooring Wet Areas	None (standard)
Flooring Dry Areas	None (standard)
All Flooring	Supplied and Installed by Site Contractor
Tile Prep	Backer-board Prep for Tile Floors (Upgrade)

DEFINITIONS

Factory =	Your home is precision-built, indoors in a dry, controlled-environment.
Site Contractor =	A Licensed California Contractor who will provide labor and some materials to complete the required work at the construction site (in direct contract with you).
PLAN (OR) PLANS =	The complete set of Factory Built Housing (commonly called "Modular") plans approved by a State of California 3rd Party Design Approval Agency as complete and ready to construct in the Factory.
Standard =	Included in the base price for the Modular home
Upgrade =	Available for an Additional expense

Décor:

Window Coverings	None
Blinds	None

Structural:

Floor Joist	2X12 Double Rims with Floor Trusses, or per PLANS
Floor Decking	23/32 Tongue & Groove OSB
Exterior Walls	2X6 - 16" On Center
Wall Height	9' first level, 8' (if applicable) second level; Per custom PLANS (Upgrade)
Interior Walls	2X4 (minimum)
Roof Pitch & Load	10/12 Roof Pitch with 30 lb roof load, or per PLANS Roof rafters & 7/16" sheathing to be shipped loose and installed by Others
Ceiling	Flat throughout Cove/Trey or Vaulted per PLANS (Upgrade)

Fire Sprinklers:

Project & PLAN Specific Engineered Design (**Upgrade**)

Energy Efficiency:

Insulation	EcoBatt® formaldehyde-free insulation from Knauf
- Floor	R-30
- Walls	R-19
- Ceiling/Roof	R-38
Radiant Barrier Roof	If required by Energy Calculations or requested (Upgrade)
Air & Vapor Barrier	Sill Seal with Vapor Barrier

Covered Porch

Per PLAN if built in Factory (**Upgrade**)
Deck Framing - Pressure Treated 2x

DEFINITIONS

Factory =	Your home is precision-built, indoors in a dry, controlled-environment.
Site Contractor =	A Licensed California Contractor who will provide labor and some materials to complete the required work at the construction site (in direct contract with you).
PLAN (OR) PLANS =	The complete set of Factory Built Housing (commonly called "Modular") plans approved by a State of California 3rd Party Design Approval Agency as complete and ready to construct in the Factory.
Standard =	Included in the base price for the Modular home
Upgrade =	Available for an Additional expense

Decking - Composite
Square Baluster - Composite
Porch Columns - Craftsman style
Fiber Cement ceiling with 2 recessed LED Lights

Attic

The attic is to be completed entirely on-site by project General Contractor. Cutting Edge Homes is providing a single-story home and doesn't provide any materials for the inside of the attic and can't provide estimates for the completion pricing of the attic by the project General Contractor.

Other Options:

From Your Imagination

Please Just Ask! The core mission of Cutting Edge Homes is to build a home that you will simply love. We want to provide options so that you are happy with your home after you move in, turning your imagination into a beautiful home for your family. If there is something that you absolutely must have in your home, please ask and we will do everything that we can to accommodate you. There are limitations to what we can provide in the Factory, but we can modify the specifications so that anything we cannot install in the Factory can be done by the Site Contractor.



DEFINITIONS

- | | |
|-------------------|---|
| Factory = | Your home is precision-built, indoors in a dry, controlled-environment. |
| Site Contractor = | A Licensed California Contractor who will provide labor and some materials to complete the required work at the construction site (in direct contract with you). |
| PLAN (OR) PLANS = | The complete set of Factory Built Housing (commonly called "Modular") plans approved by a State of California 3rd Party Design Approval Agency as complete and ready to construct in the Factory. |
| Standard = | Included in the base price for the Modular home |
| Upgrade = | Available for an Additional expense |